



Test Report: LPLC-18-350

18W Single Output Switching Power Supply

■ DESIGN VERIFY TEST

Output Function Test

Input Function Test

Protection Function Test

Component Stress Test

■ SAFETY & E.M.C. TEST

Safety Test

E.M.C. Test

■ RELIABILITY TEST

ENVIRONMENT TEST

DESIGN VERIFY TEST
OUTPUT FUNCTION TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	RIPPLE & NOISE	V1 : 300 mVp-p (Max)	I/P : 115VAC O/P : FULL LOAD Ta : 25°C	V1 : 110 mVp-p (Max)	P
2	OUTPUT VOLTAGE TOLERANCE	V1 : 5 %~ -5 % (Max)	I/P : 100 VAC / 132 VAC O/P : FULL/ MIN LOAD Ta : 25°C	V1 : 0.09 %~ -0.09 %	P
3	LINE REGULATION	V1 : 1 %~ -1 % (Max)	I/P : 100VAC ~ 132 VAC O/P : FULL LOAD Ta : 25°C	V1 : 0.02 %~ -0.02 %	P
4	LOAD REGULATION	V1 : 3 %~ -3 % (Max)	I/P : 115 VAC O/P : FULL ~MIN LOAD Ta : 25°C	V1 : 0.09 %~ -0.09 %	P
5	SET UP TIME	115VAC : 3600 ms (Max)	I/P : 115 VAC O/P : FULL LOAD Ta : 25°C	115VAC/ 2559 ms	P
6	RISE TIME	115VAC : 150 ms (Max)	I/P : 115 VAC O/P : FULL LOAD Ta : 25°C	115VAC/ 38 ms	P
7	HOLD UP TIME	115VAC : 20 ms (TYP)	I/P : 115 VAC O/P : FULL LOAD Ta : 25°C	115VAC/ 30 ms	P
8	OVER/UNDERSHOOT TEST	< ±5%	I/P : 115 VAC O/P : FULL LOAD Ta : 25°C	TEST : < 5 %	P
9	DYNAMIC LOAD	V1 : 4800 mVp-p	I/P : 115VAC O/P : FULL /Min LOAD 90%DUTY/ 1KHZ Ta : 25°C	172 mVp-p	P

INPUT FUNCTION TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	INPUT VOLTAGE RANGE	100VAC~132VAC	I/P : TESTING O/P : FULL LOAD Ta : 25°C I/P : LOW-LINE-3V= 97 V HIGH-LINE+15%=152V O/P : FULL/MIN LOAD ON : 30 Sec . OFF : 30 Sec 10MIN (AC POWER ON/OFF NO DAMAGE)	70V~132V TEST : OK	P
2	INPUT FREQUENCY RANGE	47HZ ~63 HZ NO DAMAGE OSC	I/P : 100VAC ~ 132 VAC O/P : FULL -MIN LOAD Ta : 25°C	TEST : OK	P
3	EFFICIENCY	82 % (TYP)	I/P : 115 VAC O/P : FULL LOAD Ta : 25°C	82.88 %	P
4	INPUT CURRENT	115V/ 0.5 A (TYP)	I/P : 115 VAC O/P : FULL LOAD Ta : 25°C	I = 0.3 A/ 115 VAC	P
5	INRUSH CURRENT	115V/ 40 A (TYP) COLD START	I/P : 115 VAC O/P : FULL LOAD Ta : 25°C	I = 27 A/ 115 VAC	P
6	LEAKAGE CURRENT	< 0.25 mA / 120 VAC	I/P : 132 VAC O/P : Min LOAD Ta : 25°C	L-FG : 0.01 mA N-FG : 0.01 mA	P

PROTECTION FUNCTION TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	OVER LOAD PROTECTION	95 %- 105 %	I/P : 115 VAC O/P : TESTING Ta : 25°C	98%/ 115 VAC Constant Current Limiting	P
2	OVER VOLTAGE PROTECTION	CH1 : 50.4 V- 60 V	I/P : 115 VAC O/P : MIN LOAD Ta : 25°C	57V/ 115 VAC Shut off o/p voltage, clamping by zener diode	P
3	OVER TEMPERATURE PROTECTION	SPEC : Tj 140°C typically (U1) Detect On main control IC	I/P : 115 VAC O/P : FULL LOAD	O.T.P. Active Hiccup Mode recovers automatically after temperature goes down	P
4	SHORT PROTECTION	SHORT EVERY OUTPUT 1 HOUR NO DAMAGE	I/P : 132 VAC O/P : FULL LOAD Ta : 25°C	NO DAMAGE Constant Current Limiting	P

COMPONENT STRESS TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	Power Transistor (D to S) or (C to E) Peak Voltage	U1 Rated : FSQ0365RN 650V	I/P : High-Line +3V = 135 V O/P : (1) Full Load Turn on (2) Output Short Ta : 25°C	(1) 362 V (2) 344 V	P
2	Diode Peak Voltage	D 10 Rated : 3A/600V HER306 D 11 Rated : 1N4148 75V /0.2A	I/P : High-Line +3V = 135 V O/P : (1) Full Load Turn on (2) Output Short Ta : 25°C	(1) 290 V (2) 234 V (1) 39.4 V (2) 24.2 V	P
3	Clamp Diode Peak Voltage	D 1 Rated : 1A/600V SBYV26C	I/P : High-Line +3V = 135 V O/P : (1) Dynamic Load 90%Duty/1KHz Ta : 25°C	(1) 246 V	P
4	Input Capacitor Voltage	C5 Rated : 47uF/200V 105°C KF	I/P : High-Line +3V = 135 V O/P : (1) Full Load Turn on /Off (2) Min load Turn on /Off (3) Full Load /Min load Change Ta : 25°C	(1) 182.76 V (2) 190.54 V (3) 190.21 V	P
5	Control IC Voltage Test	U1 Rated : FSQ0365RN 9V-20V	I/P : High-Line +3V = 135 V O/P : (1) Full Load Turn on /Off (2) Min load Turn on /Off (3) Full Load /Min load Change Ta : 25°C	(1) 17.488 V (2) 16.892 V (3) 16.894 V	P

■ SAFETY & E.M.C. TEST
SAFETY TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	WITHSTAND VOLTAGE	I/P-O/P : 3 KVAC/min	I/P-O/P : 3.6 KVAC/min Ta : 25°C	I/P-O/P : 0.758 mA NO DAMAGE	P
2	ISOLATION RESISTANCE	I/P-O/P : 500VDC>100MΩ	I/P-O/P : 500 VDC Ta : 25°C/70%RH	I/P-O/P : 30 GΩ NO DAMAGE	P
3	APPROVAL	TUV : Certificate NO : UL : File NO :			N/A

E.M.C TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	HARMONIC	EN61000-3-2 CLASS A	I/P : 120/115/110 VAC/50HZ O/P : 100,75,50,25% LOAD Ta : 25°C	PASS	P
2	CONDUCTION	EN55022 CLASS A	I/P : 115VAC (50HZ) O/P : FULL/50% LOAD Ta : 25°C	PASS Test by certified Lab	P
3	RADIATION	EN55022 CLASS A	I/P : 115VAC (50HZ) O/P : FULL LOAD Ta : 25°C	PASS Test by certified Lab	P
4	E.S.D	EN61000-4-2 LIGHT INDUSTRY AIR : 8KV / Contact : 4KV	I/P : 115 VAC/50HZ O/P : FULL LOAD Ta : 25°C	CRITERIA A	P
5	E.F.T	EN61000-4-4 LIGHT INDUSTRY INPUT : 1KV	I/P : 115 VAC/50HZ O/P : FULL LOAD Ta : 25°C	CRITERIA A	P
6	SURGE	IEC61000-4-5 LIGHT INDUSTRY L-N : 1KV L,N-PE : 2KV	I/P : 115 VAC/50HZ O/P : FULL LOAD Ta : 25°C	CRITERIA A	P
7	Test by certified Lab & Test Report Prepare				

RELIABILITY TEST

ENVIRONMENT TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	TEMPERATURE RISE TEST	MODEL : LPLC-18-350 1. ROOM AMBIENT BURN-IN : 1 HRS I/P : 115VAC O/P : FULL LOAD Ta=31.9 °C 2. HIGH AMBIENT BURN-IN : 2 HRS I/P : 115VAC O/P : FULL LOAD Ta=49.4 °C			P
2	LOW TEMPERATURE TURN ON TEST	TURN ON AFTER 2 HOUR	I/P : 115VAC O/P : 100 % LOAD Ta= -30 °C	TEST : OK	P
3	HIGH HUMIDITY HIGH TEMPERATURE HIGH VOLTAGE TURN ON TEST	AFTER 12 HOURS IN CHAMBER ON CONTROL 50 °C NO DAMAGE	I/P : 132 VAC O/P : FULL LOAD Ta= 50 °C HUMIDITY= 95 %R.H	TEST : OK	P
4	TEMPERATURE COEFFICIENT	± 0.2 % (0-50°C)	I/P : 115 VAC O/P : FULL LOAD	± 0.088 % (0-50°C)	P
5	STORAGE TEMPERATURE TEST	1. Thermal shock Temperature : -45°C ~ +90°C 2. Temperature change rate : 25°C / MIN 3. Dwell time low and high temperature : 30 MIN/EACH 4. Total test cycle : 5 CYCLE 5. Input/Output condition : STATIC		OK	P
6	THERMAL SHOCK TEST	1. Thermal shock Temperature : -35°C ~ +55°C 2. Temperature change rate : 25°C / MIN 3. Dwell time low and high temperature : 30 MIN/EACH 4. Total test cycle : 10 CYCLE 5. Input/Output condition : 115VAC/Full Load		OK	P

7	VIBRATION TEST	1 Carton & 1 Set (1) Waveform : Sine Wave (2) Frequency : 10-500Hz (3) Sweep Time : 12min/sweep cycle (4) Acceleration : 2G (5) Test Time : 60min in each axis (X.Y.Z) (6) Ta : 25°C	TEST : OK	P
8	CAPACITOR LIFE CYCLE	LPLC-18-350:SUPPOSE C15 IS THE MOST CRITICAL COMPONENT (1) I/P : 115VAC O/P : FULL LOAD Ta= 25 °C LIFE TIME (2) I/P : 115VAC O/P : FULL LOAD Ta= 50 °C LIFE TIME	(1) 524217.6HRS (2) 107190.4HRS	P
9	MTBF	MIL-HDBK-217F NOTICES2 PARTS COUNT TOTAL FAILURE RATE : 1200.6k HRS		P
10	DMTBF/Accelerated Life Test	Demonstration Mean Time Between Failure(Expected Life) : 20,000 hours @ Tcase 75°C; 50,000 hours @ Tcase 60°C		P

DATE	SAMPLE	TEST RESULT	TESTER	APPROVAL
2009/8/7	RD SAMPLE	PASS	SANFORD SU	VINCENT TSENG

2003/12/12 A50-F023